

Standby service is when a customer is receiving natural gas service from Peoples Natural Gas Company as a standby or back-up to an alternative fuel source (such as a well). As a requirement of receiving standby service from Peoples, your property's service line must be outfitted with a three-way valve in accordance with Section 414 of the International Fuel Gas Code. This valve acts as a safety protection that prohibits the intermingling of natural gas from the alternative source with the natural gas on the Peoples distribution system. The three-way valve is a necessary safety measure and must be installed by a qualified plumber. Please see attached drawing of an approved installation and an example of 3-way valve. Customers must contact their qualified plumber with any questions.


Please refer to Section Rate GS-SB of the Peoples tariff to view rates charged for standby service.

Below are an example of an approved three-way valve and a sketch of an approved installation.



This is a typical above ground 3 way valve installation. Using either 100% gas from the Peoples meter set, or 100% gas from the well on site.

PNG will install inlet and outlet shutoff valves on the meter set. The three way valves must always be installed below the meter shut off valve on the outlet side of the meter set. Consumers will be responsible for the installation of the three way valve by a qualified installer.



<b>PEOPLES</b> <small>PEOPLES GAS SERVICE, INC.</small> <small>1000 W. 10th Street, Oklahoma City, OK 73106</small> <small>Phone: (405) 521-1111</small>	
<small>DATE TO SCALE</small> <small>DATE</small>	<small>SCALE</small> <small>SCALE</small>
<small>PROJECT NO.</small> <small>PROJECT</small>	<small>DATE</small> <small>DATE</small>
<small>DESIGNED BY</small> <small>DESIGNED</small>	<small>CHECKED BY</small> <small>CHECKED</small>
<small>APPROVED BY</small> <small>APPROVED</small>	<small>DATE</small> <small>DATE</small>